



Green Star - Office Interiors v1.1

Emissions

Emi-1 Refrigerant Ozone Depletion Potential

Points Available	Points Claimed	CIR Submitted
2	NA	N

Credit Criteria

Up to two points are awarded where it is demonstrated that HVAC refrigerants in use have an Ozone Depletion Potential (ODP) of zero OR where no refrigerants are used, as follows:

- 1 point = 95% of all refrigerants by volume have an ODP of zero;
- 2 points = 100% of all refrigerants by volume have an ODP of zero OR no refrigerants used. This credit only applies if refrigeration equipment has been installed by the tenant, otherwise the credit is 'Not Applicable' (type "na" in the 'No. of Points Achieved' column).

Documents Provided



A letter from the mechanical subcontractor confirming that no supplementary AC was installed.

Discussion

 A letter from the mechanical subcontractor is provided as a person of relevant authority to provide confirmation that no supplementary AC was installed as he was responsible for installation of all HVAC equipment.



James L liams Pty Ltd

Air Conditioning & Mechanical Services

ACN 004 122 650 ABN 17 004 122 650

12th June 2008

Joe Karten Technical Coordinator Green Building Council of Australia Level 15, 179 Elizabeth Street Sydney, NSW 2000

Dear Joe.

This letter confirms that the HVAC system of the GBCA Tenancy Fitout at Level 15, 179 Elizabeth Street, has been altered in the following manner:

- Displacement ventilation has been installed in the fitout under a raised floor and via plenums along façade and in meeting rooms.
- Individual airflow controls have been installed in raised floor to allow for individual comfort control at each workstation.

Furthermore, I confirm that no supplementary air was specified or installed in the tenancy fitout.

Feel free to contact me with any questions you may have.

Kind regards,

Paul Glekas

Project Manager B.E. SYDU (HONS)

